NO.	PROJECT NO.	PROJECT NAME	LETTING DATE	BRIDGE TASK MANAGER	PROJECT MANAGER	PARISH	ROUTE	ON OR OFF SYSTEM	WORK TYPE (NEW/REPLACE, REHABIRE PAIR, OTHER)	NO. OF BRIDGES	BRIDGE WIDTH x LENGTH (LIST ALL BRIDGES)	MAX. SPAN LENGTH	STEEL GIRDER TYPE	STRUCTURAL METALWORK IN POUNDS	REINFORCING STEEL IN POUNDS	QUAD BEAM (FT)	TYPE II (FT)	TYPE III (FT)	TYPE IV (FT)	TYPE BT72 (FT)	TYPE BT78 (FT)	LG-25 (FT)	LG-36 (FT)	LG-45 (FT)	LG-54 (FT)	LG-63 (FT)	LG-72 (FT)	LG-78 (FT)	U BEAM (FT)	Culvert/Box (FT)	PILES 12" (FT)	PILES 14" (FT)	PILES 16" (FT)	PILES 18" (FT)	PILES 24" (FT)	PILES 30" (FT)	PILES 36" (FT)	PILES 54" (FT)	DRILLED SHAFT (FT)	STEEL PILES (FT)	STEEL SHEET PILING (SQFT)	NO. OF DISC BEARINGS	OTHER (MSE Wall) (SQFT)	Column1	OTHER (SPECIFY)
1	H.014454	LA 15: BOEUF RIVER BRIDGE REPL (HBI)	7/14/2021	GAUDRY, CARL	MORVANT, RYAN	Richland	LA 15	ON	Replace	1	40x500	100		392	201,218										1,990							160		1,536		1,744									
2	H.000665	UP R.R. OVERPASS NEAR BONITA (HBI)	8/11/2021	BAMUGO, ANTHONY	MASTIN, CATHERINE	Morehouse	US 165	ON	REPLACE	2	34.5x100, 34.5x220	20			118,892																			4,248											16,083
3	H.010668	MILLION DOLLAR RD/HOSMER MILL RD BRIDGES	8/11/2021	DELATTE, BRIAN	OSTUNO, BARBARA	St. Tammany		OFF	REPLACE	2	28x240, 28x200	60																																	
4	H.012880	HAPSBURG LANE / COULEE	8/11/2021	DELATTE, BRIAN	OSTUNO, BARBARA	Lafayette		OFF	REPLACE	1	24X60	20		0	8,635																				960										
5	H.013081	ROUNDHILL ROAD OVER LITTLE COLEWA BAYOU	8/11/2021	DELATTE, BRIAN	OSTUNO, BARBARA	West Carroll		OFF	REPLACE	1	28x60	20			24,965																	1,040													
6	H.002980	I-10 OVERPASS OVER US 165 & MP R.R	9/8/2021	ALLEN, BRIAN	DELATTE, BRIAN	Jefferson Davis	I-10	ON	Replace	2	72x768; 72x778	131		2032	1222348										6662	6948													5880		65800					
7	H.009486	US 90: BAYOU BRIDGE	9/8/2021	BAMUGO, ANTHONY	ALLEN, BRIAN	Jefferson Davis	US 90	ON	REPLACE	1	42.5x100	20			47,000																			2,250											
8	H.010017	US 90Z: WESTBANK EXPRESSWAY REHAB	9/8/2021	GUIDRY, CHRIS	RANCK, AMANDA	Jefferson	US 90-Z	ON																																					No Info
9	H.010724	PECAN ISLAND ROAD BRIDGE OVER THE CHENAL	9/8/2021	DELATTE, BRIAN	OSTUNO, BARBARA	Pointe Coupee		OFF	REPLACE	1	16x150	25			31,468																		2,408												
10	H.011087	WESTDALE PLANTATION ROAD / BAYOU PIERRE	9/8/2021	DELATTE, BRIAN	OSTUNO, BARBARA	Red River		OFF	REPLACE	1			QUAD BEAM	164616	86,858	17,778																		2,800											
11	H.011534	WEST LOYOLA & METAIRIE HEIGHTS BRIDGES	9/8/2021	DELATTE, BRIAN	OSTUNO, BARBARA	Jefferson		OFF	REPLACE	1	28X60	20			36,867															50															
12	H.014212	I-10: ATCHAFALAYA BRS NAVIG LIGHT REPL	9/8/2021	ARMENTOR, MICHAEL	TULLIER, DANNY	Iberville, St. Martin	I-10	ON	NEW/REPLA	4																																			No Info
13	H.014592	I-10: SABINE RIVER BRIDGES REHAB	9/30/2021	VAUGHT, PAUL	VAUGHT, PAUL	Calcasieu	I-10	ON	REHAB	2	56.8 x 5007; 56.8 x 5007	288289																																	
14	H.001881	LA 392 BRIDGES NEAR HORNBECK	10/13/2021	GAUDRY, CARL	ALLEN, BRIAN	Vernon	LA 392	ON	Replace	2	32x100, 32x220	20			118,892																		4,248												
15	H.006338	HOLTON HARRIS ROAD BRIDGE	10/13/2021	DELATTE, BRIAN	OSTUNO, BARBARA	Vernon		OFF	REPLACE	1	24X80	20			27420																	1,400												
16	H.010597	SLIGO ROAD BRIDGES	10/13/2021	DELATTE, BRIAN	OSTUNO, BARBARA	West Feliciana		OFF	REPLACE	2	24X480, 24X120	40	QUAD BEAM	2462	180,582	2,963																		4,292											
17	H.011522	FAITH BAPTIST MISSION & BILL BELT ROADS	10/13/2021	DELATTE, BRIAN	OSTUNO, BARBARA	Avoyelles		OFF	REPLACE	2	28X80, 28X60	20			63,433																2,040														
18	H.014052	LA 151: I-20 OVERPASS DECK REPLACEMENT	10/13/2021	ALLEN, BRIAN	TULLIER, DANNY	Ouachita	LA 151	ON	Rehab	1	28' x 297'	70'	Steel I-Beam	13,800	61,000																														
19	H.014406	LA 661: HOUMA NAV MB ELECTRICAL REPAIR	11/10/2021	LEBOURGEOIS, CHRISTOPHER	FUNG, AGNES	Terrebonne	LA 661	ON		0																																			
20	H.014672	I-12: LA 1032 OVERPASS REPAIR	11/10/2021	LANDRY, LAUDUN	BOURGEOIS, COREY	Livingston	I-12	ON	Repair	1	150' x 61'	50'		TBD	TBD		50																												
21	H.000382	US 71: BRIDGES NEAR ST. MAURICE	12/8/2021	GRASSO, PHILLIP	ALLEN, BRIAN	Natchitoches, Winn	US 71	ON	REPLACE	3	40' x 240; 40' x 500, & 40' x 140'	100		500	610,000							1,422			2,488									5,330				1,900							
22	H.001820	LA 485: BRIDGES NEAR ALLEN	12/8/2021	BAMUGO, ANTHONY	YANG, LI	Natchitoches	LA 485	ON	REPLACE	7	37.5x160, 37.5x200, 37.5x140, 34.5x120, 96x32, 96x32	20			383,522																180				9,498										
23	H.008118	LA 653: BAYOU DUMAR BRIDGE REPLACEMENT	12/8/2021	MCADAMS, MARY	ALLEN, BRIAN	Lafourche	LA 653	ON	Replacement	1	30' x 140'	20'			128,271																			3,584											
24	H.009489	US 61: JEFFERSON HIGHWAY OVERPASS REPAIR	12/8/2021	BUCCI, MARK	RANCK, AMANDA	East Baton Rouge	US 61	ON	REPAIR	1	30'X320'	70'	Steel Plate Girder and Rolled Shapes	36225																									480						
25	H.010562	BANK STREET BRIDGE	12/8/2021	DELATTE, BRIAN	OSTUNO, BARBARA	East Feliciana		OFF	REPLACE	0																				44															
26	H.011487	LA 182: BERWICK BAY BRIDGE REHAB (HBI)	12/8/2021	BOURGEOIS, COREY	GUIDRY, CHRIS	St. Mary	LA 182	ON	REHAB	1	3745X25	608	TRUSS	4200	42,500																														
27	H.013080	MCLEMORE ROAD OVER BEE BAYOU	12/8/2021	DELATTE, BRIAN	OSTUNO, BARBARA	Richland		OFF	REPLACE	1	24X120	20			40,541																	2,016													
28	H.013140	EIGHTY ARPENT ROAD OVER UNNAMED COULEE	12/8/2021	DELATTE, BRIAN	OSTUNO, BARBARA	Iberia		OFF	REPLACE	1	28X80	20																																	
29	H.001799	LA 531 OVERPASS	1/12/2022	HERATH, ANANDA	FUSILIER, JACOB	Webster	I-20, LA 531	ON			34.5x180	90			123,434									x																					
30	H.010867	JUDE & PLACIDE ROAD BRIDGES	1/12/2022	DELATTE, BRIAN	OSTUNO, BARBARA	Vermilion		OFF	REPLACE	2	28X50, 28X60	25			17,215																	1,152	990												
31	H.012469	US 190: MRB - NAVIG LIGHT REPL (HBI)	1/12/2022	LEBOURGEOIS, CHRISTOPHER	GUIDRY, CHRIS	East Baton Rouge	US 190	ON	REHAB	1	5880X88	748	TRUSS																																
32	H.013142	CHES COURVILLE RD OVER COULEE NICOLE G.	1/12/2022	DELATTE, BRIAN	OSTUNO, BARBARA	St. Martin		OFF	REPLACE	1	22.3X38	20			43,258																												TBD		
33	H.013952	JESSE B ROAD OVER BAYOU MALLET	1/12/2022	BOURGEOIS, COREY	RANCK, AMANDA	St. Landry		OFF	Replace	1	60' x 24'	20'			18059																	1,440													
34	H.013956	BEAMOW ROAD OVER BAYOU MARINGOUIN	1/12/2022	BOURGEOIS, COREY	RANCK, AMANDA	Pointe Coupee		OFF	Replace	1	84' x 24'	28'			41066																	1,280													
35	H.013957	SLIGO ROAD OVER WALTER CREEK	1/12/2022	BOURGEOIS, COREY	RANCK, AMANDA	West Feliciana		OFF	Replace	1					2942															96															
36	H.013958	CARPENTERS BR RD OVER WHISKEY CHITTO CR	1/12/2022	BOURGEOIS, COREY	RANCK, AMANDA	Allen		OFF	Replace	1	322' x 28'	46'			TBD							319											TBD												
37	H.013959	REEDS BR RD OVER CALCASIEU RIVER RELIEF	1/12/2022	BOURGEOIS, COREY	RANCK, AMANDA	Allen		OFF	Replace	1	120' x 24'	20'			TBD																		TBD												
38	H.013989	GRAYBOW ROAD OVER PALMETTO CREEK	1/12/2022	BOURGEOIS, COREY	RANCK, AMANDA	Beauregard		OFF	Replace	1	80' x 28'	20'			TBD																		TBD												
39	H.013997	LOC RD OVER BORROW PIT(BLIND RV BT LNCH)	1/12/2022	BOURGEOIS, COREY	RANCK, AMANDA	St. James		OFF	Replace	1	80' x 24'	20'			TBD																		TBD												
40	H.014465	LA 82: VERMILION RIVER MB RH(PERRY)(HBI)	2/9/2022	BRAUNER, KURT	HINGLE, STEWART	Vermilion	LA 82	ON						37000	24,000																180		650												
41	H.014588	I-20: ORANGE ST OVERPASS REPAIR	2/9/2022	EL KASSOUF, MARK	BOURGEOIS, COREY	Ouachita	I-20	ON	Repair	1	359' x 40'	123'		TBD	TBD																														
42	H.002184	BAYOU CHENAL & BAYOU DISCHARGE BRS.	3/9/2022	BAMUGO, ANTHONY	MOORE, DARRELL	Pointe Coupee	LA 413	ON	REPLACE	2	24.3X220; 34.5x180	20			161,774																			7,750											
43	H.002365	LA 63 BRIDGES NEAR BLUFF CREEK	3/9/2022	EL KASSOUF, MARK	ALLEN, BRIAN	East Feliciana	LA 63	ON																																					
44	H.011965	LA 47: IWGO BRIDGE REHABILITATION (HBI)	3/9/2022	KEMP, KELLY	BABAIZADEH, HAMED	Orleans	LA 47	ON	Rehab	1	(2X29' bounds) 58' x 6622'	702																																	The scope of repairs has not been finalized.
45	H.013118	HILL AVENUE OVER DRAINAGE CANAL	3/9/2022	DELATTE, BRIAN	OSTUNO, BARBARA	Morehouse		OFF		0																				200															
46	H.013120	BETHEL ROAD OVER SLASH BAYOU TRIBUTARY	3/9/2022	DELATTE, BRIAN	OSTUNO, BARBARA	Rapides		OFF		TBD		TBD			TBD																	TBD													
47	H.013842	CAUSEWAY BLVD - EARHART EXPRESSWAY PH 1A	3/9/2022	LANCASTER, ADAM	YANG, LI	Jefferson	LA 3046, LA 3139	ON	WIDENING	1	1300 x 56	75	W24, W27, W30, W33, W36	2744337	1318768																	153186		227911											
48	H.014288	LA 82:MERMENTAU MB REHAB(G CHENIER)(HBI)	3/9/2022	METCALF, WILLIAM	TULLIER, DANNY	Cameron	LA 82	ON																																					Project scope not finalized.
49	H.014323	I-10: MISS RIVER BR FENDER REP. (PIER 6)	3/9/2022	LANDRY, LAUDUN	BRAUNER, KURT	East Baton Rouge	I-10	ON	Rehab/Repair																																				
50	H.001666	DORCHEAT BAYOU BRIDGE	4/13/2022	LANDRY, LAUDUN	TOURRES, VALERIE	Webster	LA 160	ON	replace	4	40x'x30', 120'x30', 140'x30', 120'x30'	20'			279259																		4480	6960											
51	H.001970	BOEUF RIVER BRIDGE NEAR HEBERT	4/13/2022	BOURGEOIS, COREY	TOURRES, VALERIE	Richland	LA 561	ON	replace	1	702'x32'	111'													2796													TBD							
52	H.009498	LA 121: CALCASIEU RIVER BRIDGE	4/13/2022	KREBS, JOHN	ALLEN, BRIAN	Rapides	LA 121	ON		3	480' x 42.5'; 480' x 42.5'; 240' x 42.5'	60'	2000	497160									5950								720				6780										
53	H.010673	US90Z:HARVEY CANAL TUNNEL REHABILITATION	4/13/2022	TOURRES, VALERIE	FUSILIER, JACOB	Jefferson	US 90-Z	ON	rehab																																				No Information
54	H.013273	LA 8: OUACHITA RIVER BRIDGE SCOUR REPAIR	4/13/2022	DOOLITTLE, STEPHANIE	BAMUGO, ANTHONY	Catahoula	LA 8	ON	Scour	0																																			
55	H.013832	LA 6: GRAND ECORE BRIDGE DECK REPAIR	4/13/2022	MCADAMS, MARY	D'ANDREA, ARTUR	Natchitoches	LA 6	ON	Rehab	1	28' x 975'	375'																																	Project scope not finalized yet.
56	H.013947	ATKINS ROAD OVER JOES BAYOU	4/13/2022	ALLEN, BRIAN	TOURRES, VALERIE	Madison		OFF		1	28' x 140'	20'																				2720													
57	H.013953	MCMANUS ROAD OVER CYPRESS CREEK	4/13/2022	ALLEN, BRIAN	TOURRES, VALERIE	Richland		OFF		1	28' x 160'	20'																				2592													
58	H.013954	PLEASANT RIDGE RD OVER RABBIT BRANCH	4/13/2022	ALLEN, BRIAN	TOURRES, VALERIE	LaSalle		OFF		1	24' x 60'	20'																				1040													
59	H.013955	LA 961: SANDY CREEK BRIDGE	4/13/2022	BOURGEOIS, COREY	RANCK, AMANDA	East Feliciana	LA 961	ON	Replace	1	140' x 32'	20'			50991																		2,240													
60	H.013963	LA 384: CANAL BRIDGE	4/13/2022	BOURGEOIS, COREY	RANCK, AMANDA	Cameron	LA 384	ON	Replace	1					TBD															TBD															
61	H.013966	LA 321: CREEK BRIDGES	4/13/2022	BOURGEOIS, COREY	RANCK, AMANDA	St. Martin	LA 321	ON	Replace	3	80' x 30'	20'			36499															188				1,400											
62	H.013994	OAK HALL RD OVER BAYOU BOEUF	4/13/2022	ALLEN, BRIAN	TOURRES, VALERIE	Avoyelles		OFF		1	28' x 140'	20'																				3040													
63	H.010557	LAJAUNIE RD / LATERAL 1 BAYOU ST. CLAIR	5/11/2022	DELATTE, BRIAN	OSTUNO, BARBARA	Lafayette		OFF		1	28X40; 28X40	20			24684																		1260													
64	H.013098	JIM CRYER LANE OVER BAYOU ANACOCO	5/11/2022	DELATTE, BRIAN	OSTUNO, BARBARA	Vernon		OFF		1	28X240	48	LG 25		TBD							TBD											TBD													
65	H.006128	VIDA SHAW BRIDGE OVER BAYOU TECHE	6/8/2022	TBD	OSTUNO, BARBARA	Iberia		OFF																																					
66	H.010005	LA733:VRMLN R MB RH(ELOI BROUSSARD)(HBI)	6/8/2022	BRAUNER, KURT	HINGLE, STEWART	Lafayette	LA 733	ON						37000	24000																180		650													
67	H.012071	US 51: YELLOW WATER RIVER BRIDGE	6/8/2022	LANDRY, LAUDUN	BOURGEOIS, COREY	Tangipahoa	US 51	ON	Replace	1	160' x 72.5'	20'		TBD	TBD																			TBD												
68	H.013111	DORCHEAT ROAD OVER CANEY CREEK	6/8/2022	DELATTE, BRIAN	OSTUNO, BARBARA	Webster		OFF		1	28X100	20			38005																	TBD													
69	H.013948	LA 1183: TURNER CANAL BRIDGE	6/8/2022	ALLEN, BRIAN	TOURRES, VALERIE	Avoyelles	LA 1183	ON		1	30' x 100'	20'			37386																		2112													
70	H.013949	LA 1226: BAYOU CHEVREUILLE BRIDGE	6/8/2022	ALLEN, BRIAN	TOURRES, VALERIE	Natchitoches	LA 1226	ON		1	30' x 140'	20'			39781																		2600													
71	H.013968	LA 404: BAYOU AND CANAL BRIDGES	6/8/2022	BOURGEOIS, COREY	RANCK, AMANDA	Iberville	LA 404	ON	Replace	4	140' x 30', 160' x 30', 80' x 30'	20'			TBD															TBD				TBD													
72	H.013976	LA 376: BAYOU BRIDGES	6/8/2022	BOURGEOIS, COREY	RANCK, AMANDA	Evangeline	LA 376	ON	Replace	2	80' x 28'	20'			TBD															TBD				TBD													
73	H.013982	LA 10 SPUR, LA 1042: BRS NEAR GREENSBURG	6/8/2022	BOURGEOIS, COREY	RANCK, AMANDA	St. Helena	LA 1042, LA 10-S	ON	Replace	4	60' x 30', 180' x 30'	20'			TBD															TBD				TBD													
74	H.013985	LOCAL:PRAIRIE BAYOU AND DRAINAGE BRIDGES	6/8/2022	ALLEN, BRIAN	TOURRES, VALERIE	Avoyelles		OFF		3	24' x 80', 24' x 80', 24' x 60'	20'			65539																		2800													
75	H.000186	US 90 OVER I-10 RAMPS @ LOCKMOOR (HBI)	7/13/2022	WANG, XUYONG	YANG, LI	Calcasieu	US 90	ON	REPLACE	1	42x1178	187	STEEL PLATE GIRDER	2774500	500600									975		1230												1200							
76	H.000413	CROSS BAYOU BRIDGE REPLACEMENT	7/13/2022	WINDMANN, ANDREW	BABAIZADEH, HAMED	Caddo	US 71	ON																																					Project scope not yet determined.
77	H.000445	US 190: UPRR OVERPASS NEAR OPELOUSAS	7/13/2022	GAUDRY, CARL	ALLEN, BRIAN	St. Landry	US 190	ON	Replace	3	36'x420', 36'x420', 104'x150'	100		TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	
78	H.001553	LA 146 BRIDGES NEAR KELLEYS	7/13/2022	EL KASSOUF, MARK	ALLEN, BRIAN	Jackson	LA 4, LA 146	ON																																					
79	H.001711	SALINE BAYOU RELIEF & MILL CR. BRS.	7/13/2022	BUCCI, MARK	YANG, LI	Winn	LA 126	ON	REPLACE	3	34'x140', 34'x120', 34'x140'	20'			380000																		6860													
80	H.001961	JOES BAYOU & CARRAWAY LAKE BRIDGES	7/13/2022	BAMUGO, ANTHONY	ALLEN, BRIAN	East Carroll	LA 134	ON	REPLACE	2	32X220, 32X120	20			126111																			4560												
81	H.002176	LA 10 BRIDGES	7/13/2022	EL KASSOUF, MARK	ALLEN, BRIAN	St. Landry	LA 10	ON																																					
82	H.002264	LA 302: BAYOU BARATARIA MB REPLACEMENT	7/13/2022	MICHAEL, ANDREW	YANG, LI	Jefferson	LA 3257, LA 302-P, LA 45	ON		1	32' x 963'	183'	Swing span (Plate Girders and Rolled Shapes)	300000	170000								3120											3000	4500											
83	H.007963	BLACKWATER BAYOU BRIDGE	7/13/2022	GAUDRY, CARL	DELATTE, BRIAN	East Baton Rouge	LA 410	ON	Replace	1	32x120	20			44248																			2100												
84	H.008170	LA 1024 CREEK BRS. NEAR FRIENDSHIP	7/13/2022	WINDMANN, ANDREW	JUDICE, ANDREW	Livingston	LA 1024	ON	REPLACE	1	26.5x140	20			40783																		3200													
85	H.008203	LA 835 CREEK BRIDGES	7/13/2022	KREBS, JOHN	MASTIN, CATHERINE	Morehouse	LA 835	ON	REPLACE	2	32' x 100'	20'		500	42000															86				1368											159.65 (SHB span conc. CY)	
86	H.008288	BOEUF RIVER BRIDGE NEAR BUCKNER (HBI)	7/13/2022	BOOTHE, JOHN	TOURRES, VALERIE	Richland	LA 132	ON	Replace	1	30'x425'	85'		506	145,602									1,690							100			1,312	1,472											
87	H.008358	BLACK BAYOU BRS NEAR MADISONVILLE	7/13/2022	GAUDRY, CARL	TOURRES, VALERIE	St. Tammany	LA 1077	ON	Replace	1	24x140	20			40783																		3200													
88	H.008449	DRAIN BRIDGE NEAR STONEY POINT	7/13/2022	GAUDRY, CARL	MOORE, DARRELL	Washington	LA 450	ON	Replace	1	Culvert																																	4-10'x8'x86'	
89	H.009122	LA1204:BAYOU FLAGON & KITCHEN CR BRIDGES	7/13/2022	BABAIZADEH, HAMED	YANG, LI	Rapides	LA 1204	ON	Replace	2	40' x 576', 40' x 100'	48'		3729	299913		2850																TBD		TBD	TBD										
90	H.010006	LA 58: PETIT CAILLOU MB RH (SARAH)(HBI)	7/13/2022	BRAUNER, KURT	HINGLE, STEWART	Terrebonne	LA 58	ON						37200	24442																186		656													
91	H.012083	I-10: CALCASIEU RIVER BRIDGE INT REPAIRS	7/13/2022	WANG, XUYONG	BABAIZADEH, HAMED	Calcasieu	I-10	ON	Rehab	1	(2X26' bounds) 52' x 6617'-1"	420																																	The scope of repairs has not been finalized.
92	H.012447	LA 182: B LAFOURCHE MB RH(RACELAND)(HBI)	7/13/2022	WINDMANN, ANDREW	BRIGNAC, CHRISTINA	Lafourche	LA 182	ON																																					Project scope not yet determined.
93	H.013458	MANCHAC ACRES RD & H H WILSON RD BRIDGES	7/13/2022	DELATTE, BRIAN	OSTUNO, BARBARA	Ascension		OFF		0																				50, 44															
94	H.013979	LA 518, LOCAL: BRIDGES NEAR ATHENS	7/13/2022	ALLEN, BRIAN	TOURRES, VALERIE	Claiborne	LA 518	ON		3	32' x 100', 32' x 140', 24' x 60'	20'			230144																	800	2800												
95	H.013987	LA 521: BRIDGES NEAR DYKESVILLE	7/13/2022	ALLEN, BRIAN	TOURRES, VALERIE	Claiborne	LA 521	ON		3	32' x 96', 32' x 100', 32' x 140'	20'			120580																		4248													
96	H.014214	SINGLETARY ST. OVER REDWOOD CREEK	7/13/2022	DELATTE, BRIAN	OSTUNO, BARBARA	East Feliciana		OFF																																					
97	H.014281	US 190: MISS RIVER BR REPAIR PH. 3 (HBI)	7/13/2022	EL KASSOUF, MARK	GUIDRY, CHRIS	East Baton Rouge	US 190	ON	REHAB	1	5880X88	748	TRUSS																																
98	H.014284	LA 301: PRIEST CANAL BRIDGE	7/13/2022	BOURGEOIS, COREY	ALLEN, BRIAN	Jefferson	LA 301	ON	Replace	1	80' x 32'	20'																					TBD													No Info

NO.	PROJECT NO.	PROJECT NAME	LETTING DATE	BRIDGE TASK MANAGER	PROJECT MANAGER	PARISH	ROUTE	ON OR OFF SYSTEM	WORK TYPE (NEW/REPLACE, REHABIRE PAIR, OTHER)	NO. OF BRIDGES	BRIDGE WIDTH x LENGTH (LIST ALL BRIDGES)	MAX. SPAN LENGTH	STEEL GIRDER TYPE	STRUCTURAL METAL/WORK IN POUNDS	REINFORCING STEEL IN POUNDS	QUAD BEAM (FT)	TYPE II (FT)	TYPE III (FT)	TYPE IV (FT)	TYPE BT72 (FT)	TYPE BT78 (FT)	LG-25 (FT)	LG-36 (FT)	LG-45 (FT)	LG-54 (FT)	LG-63 (FT)	LG-72 (FT)	LG-78 (FT)	U BEAM (FT)	Culvert/Box (FT)	PILES 12" (FT)	PILES 14" (FT)	PILES 16" (FT)	PILES 18" (FT)	PILES 24" (FT)	PILES 30" (FT)	PILES 36" (FT)	PILES 54" (FT)	DRILLED SHAFT (FT)	STEEL PILES (FT)	STEEL SHEET PILING (SQFT)	NO. OF DISC BEARINGS	OTHER (MSE Wall) (SQFT)	Column1	OTHER (SPECIFY)
99	H.014560	LA 94: VERMILION RIVER BRIDGE REPL.	7/13/2022	TOURRES, VALERIE	BAMUGO, ANTHONY	Lafayette, St. Martin	LA 94	ON	REPLACE	0																																				
100	H.014633	LA 29: BAYOU COCODRIE BRIDGES SCOUR RE	7/13/2022	TOURRES, VALERIE	BAMUGO, ANTHONY	St. Landry	LA 29	ON	SCOUR	1																																				
101	H.013970	LA 717: KLONDIKE CANAL AND BAYOU BRIDGES	8/10/2022	BOURGEOIS, COREY	RANCK, AMANDA	Cameron	LA 717	ON	Replace	2	100' x 30', 80' x 30'	20'			TBD																			TBD													
102	H.013984	LA 16: BRIDGES (ISABEL TO SUN)	8/10/2022	BOURGEOIS, COREY	RANCK, AMANDA	St. Tammany, Washington	LA 16	ON	Replace	5	200' x 30', 200' x 30, 60' x 30', 200' x 30', 260' x 30'	20'			TBD																			TBD													
103	H.002794	LA 308: CANAL BRIDGES NEAR LAROSE	9/14/2022	CHEN, YANLIN	JUDICE, ANDREW	Lafourche	LA 308	ON	REPLACE	3	30'x160', 30'X100', 30'X120'	20'			140963																			6160							3500						
104	H.013942	LA 9:MIDDLE FORK BAYOU AND CREEK BRIDGES	9/14/2022	ALLEN, BRIAN	TOURRES, VALERIE	Claiborne	LA 9	ON		3	40' x 195', 40' x 273', 40' x 234'	39'			581886							3420												360	6300												
105	H.013986	LA 155: BRIDGES NEAR COUSHATTA	9/14/2022	ALLEN, BRIAN	TOURRES, VALERIE	Red River	LA 155	ON		4	40' x 140', 40' x 340', 32' x 140', 32' x 140'	20'			320222																			9450													
106	H.013992	LA 151: CREEK AND RELIEF BRIDGES	9/14/2022	ALLEN, BRIAN	TOURRES, VALERIE	Lincoln, Union	LA 151	ON		4	32' x 120', 32' x 120', 32' x 120', 32' x 60'	20'			164376																			7860													
107	H.013996	LA 1074, LA 1075: BRIDGES NEAR RIO	9/14/2022	BOURGEOIS, COREY	RANCK, AMANDA	Washington	LA 1074, LA 1075	ON	Replace	4	100' x 30', 180' x 30', 100' x 30', 80' x 30'	20'			TBD																			TBD													
108	H.002238	LA 56: ROBINSON CANAL BRIDGE	10/12/2022	HERATH, ANANDA	RANCK, AMANDA	Terrebonne	LA 56	ON		1	34.5x260	20																																		
109	H.013988	LA 534: BRIDGES (LA 2 TO HAYNESVILLE)	11/9/2022	ALLEN, BRIAN	TOURRES, VALERIE	Claiborne	LA 534, LA 534-S	ON		8	32' x 60'; 32' x 80'; 32' x 80'; 32' x 80'; 32' x 80'; 32' x 80'; 32' x 100'	20'			262707															336					12456												
110	H.013990	LA 132: BRIDGES NEAR MANGHAM	11/9/2022	ALLEN, BRIAN	TOURRES, VALERIE	Richland	LA 132	ON		5	36' x 100', 36' x 80', 36' x 60', 36' x 80', 36' x 120'	20'			186441																			11880													
111	H.013995	LA 507, LA 514, LOCAL: BAYOU AND CR BRS	11/9/2022	ALLEN, BRIAN	TOURRES, VALERIE	Bienville, Red River	LA 507, LA 514	ON		6	32' x 100', 32' x 100', 32' x 100', 32' x 120', 32' x 60', 24' x 80'	20'																																		
112	H.010358	US 190: LA 415 & RR OVERPASS REPL (HBI)	12/14/2022	MICHAEL, ANDREW	FUSILIER, JACOB	West Baton Rouge	US 190	ON		1	82' X 1960'	150'			1400000											27300								29000				2700									
113	H.012066	LA 3213: GRAMERCY BRIDGE REHABILITATION	12/14/2022	GUIDRY, CHRIS	ALLEN, BRIAN	St. James	LA 3213	ON	REHAB	1	3010X76	1462	TRUSS	5000																																
114	H.012541	LA 594: OVERPASS I-20	12/14/2022	GUIDRY, CHRIS	MOSS, SARAH	Ouachita	LA 594	ON	REPLACE	1	462X48	93		200	290000								3234															345									
115	H.013122	PINE ST. & HARRISON/COLLIER BRIDGES	12/14/2022	DELATTE, BRIAN	OSTUNO, BARBARA	Ouachita		OFF																																						
116	H.013127	BRITTON RD & HERMAN DICKERSON RD BRS	12/14/2022	DELATTE, BRIAN	OSTUNO, BARBARA	Ouachita		OFF																																						
117	H.013130	RED CUT RD & CHARLES RAWLS RD BRIDGES	12/14/2022	DELATTE, BRIAN	OSTUNO, BARBARA	Ouachita		OFF																																						
118	H.013137	HARMON JOHNSON RD & GOOD HOPE RD BRS	12/14/2022	DELATTE, BRIAN	OSTUNO, BARBARA	Ouachita		OFF																																						
119	H.013143	CARBON PLANT ROAD OVER BAYOU BOEUF	12/14/2022	DELATTE, BRIAN	OSTUNO, BARBARA	Avoyelles		OFF																																						
120	H.013144	PINE BLUFF RD & TACK ALLEN RD BRIDGES	12/14/2022	DELATTE, BRIAN	OSTUNO, BARBARA	Ouachita		OFF																																						
121	H.013163	WADESBORO ROAD OVER UNNAMED CREEK	12/14/2022	DELATTE, BRIAN	OSTUNO, BARBARA	Tangipahoa		OFF																																						
122	H.013199	COUNTRY ESTATES DR OVER ST. LOUIS BAYOU	12/14/2022	DELATTE, BRIAN	OSTUNO, BARBARA	Terrebonne		OFF		1	28X100	20			TBD																	TBD														
123	H.013821	LA 6: YOUNGS BAYOU BRIDGES REHAB	12/14/2022	CHEN, YANLIN	TOURRES, VALERIE	Natchitoches	LA 6	ON	REPAIR	2		20'																																	Project has not been scoped.	
124	H.014283	US 90: IHNC MB REHAB PH. 2 (DANZIGER)	12/14/2022	BUCCI, MARK	HINGLE, STEWART	Orleans	US 90	ON	REHAB	1																																			Project has not been scoped.	
125	H.014318	GURNEY ROAD BRIDGES	12/14/2022	DELATTE, BRIAN	OSTUNO, BARBARA	East Baton Rouge		OFF		TBD	TBD				TBD																	TBD														
126	H.014319	CEDARCREST AVENUE OVER WEINER CREEK	12/14/2022	DELATTE, BRIAN	OSTUNO, BARBARA	East Baton Rouge		OFF		TBD	TBD				TBD																	TBD														
127	H.014320	VAN BUREN STREET OVER CORPORATION CANAL	12/14/2022	DELATTE, BRIAN	OSTUNO, BARBARA	East Baton Rouge		OFF		TBD	TBD				TBD																	TBD														
128	H.014322	CENTURION AVE OVER DRAINAGE BAYOU	12/14/2022	DELATTE, BRIAN	OSTUNO, BARBARA	East Baton Rouge		OFF		TBD	TBD				TBD																	TBD														
129	H.014337	ACADIAN HILLS LANE OVER DRAINAGE CANAL	12/14/2022	DELATTE, BRIAN	OSTUNO, BARBARA	Lafayette		OFF			TBD				TBD																	TBD														
130	H.014591	I-12: US 61 BRIDGES GIRDER REPAIRS	12/14/2022	LANDRY, LAUDUN	GAUDRY, CARL	East Baton Rouge	I-12	ON	REPAIR	1	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	Feasibility Phase
131	H.002337	LA 327-S: BAYOU FOUNTAIN	1/11/2023	LANDRY, LAUDUN	MOORE, DARRELL	East Baton Rouge	LA 327-S	ON	Replace	1	40.21' x 100'	20'			36660																			3000													
132	H.014280	US 90: BAYOU RAMOS REHAB. PHASE III	1/11/2023	FENG, DANA	TULLIER, DANNY	St. Mary	US 90	ON																																						
133	H.001674	LA 146 BRIDGES NEAR HOMER	1/13/2023	MUSTAQUE, AHMED	BABAIZADEH, HAMED	Claiborne	LA 146	ON	Replace	4	32'x120', 32'x80', 32'x120, 32'x160	20																																		
134	H.010015	LA 143: BAYOU D'ARBONNE BRIDGE	3/8/2023	BOURGEOIS, COREY	TOURRES, VALERIE	Ouachita	LA 143	ON	replace	1	700'x44'	100'			TBD									4179															TBD									
135	H.002244	LA 56: BOUDREAUX CANAL MB REPLACEMENT	6/14/2023	GRASSO, PHILLIP	FUSILIER, JACOB	Terrebonne	LA 56	ON			32 x 1,123	183	Swing Span (Plate Girders and Rolled Shapes)	300000	455000								4000	500											3600	3740	2720				TBD						
136	H.014220	NATION ROAD OVER COULEE DURALDE	6/14/2023	DELATTE, BRIAN	OSTUNO, BARBARA	Acadia		OFF		1	28X100	20			TBD																	TBD														
137	H.014223	CAMILE ROAD OVER BAYOU GRAND MARAIS	6/14/2023	DELATTE, BRIAN	OSTUNO, BARBARA	Vermilion		OFF		TBD	TBD	TBD			TBD																	TBD														
138	H.014226	AUGUILLARD ROAD OVER COULEE	6/14/2023	DELATTE, BRIAN	OSTUNO, BARBARA	St. Martin		OFF		1	28X100	20			TBD																	TBD														
139	H.014229	CRAWFORD ROAD OVER TIGER BRANCH	6/14/2023	DELATTE, BRIAN	OSTUNO, BARBARA	Caddo		OFF		1	28X100	20			TBD																	TBD														
140	H.014232	RUFFIN DRIVE OVER DRAIN TO YOUNGS BAYOU	6/14/2023	DELATTE, BRIAN	OSTUNO, BARBARA	Ouachita		OFF		1	28X100	20			TBD																	TBD														
141	H.014234	COMEAUX ROAD OVER STEEP BAYOU	6/14/2023	DELATTE, BRIAN	OSTUNO, BARBARA	Richland		OFF		TBD	TBD	TBD			TBD																	TBD														
142	H.014235	WEST RACCA RD OVER E GRAND MARAIS DITCH	6/14/2023	DELATTE, BRIAN	OSTUNO, BARBARA	Jefferson Davis		OFF		1	TBD	TBD			TBD																	TBD														
143	H.014255	BEESON ROAD OVER FLAGON BAYOU TRIBUTARY	6/14/2023	DELATTE, BRIAN	OSTUNO, BARBARA	Rapides		OFF																																						
144	H.014261	DOSHIE ROAD OVER CHERRY WINCHE CRK TRIB	6/14/2023	DELATTE, BRIAN	OSTUNO, BARBARA	Rapides		OFF																																						
145	H.014262	RANDALL ROAD OVER YELLOW WATER RIVER	6/14/2023	DELATTE, BRIAN	OSTUNO, BARBARA	Tangipahoa		OFF																																						
146	H.014263	N. HOOVER ROAD OVER UNNAMED CREEK	6/14/2023	DELATTE, BRIAN	OSTUNO, BARBARA	Tangipahoa		OFF																																						
147	H.014265	NORTH RIVER ROAD OVER IRVING BRANCH	6/14/2023	DELATTE, BRIAN	OSTUNO, BARBARA	Tangipahoa		OFF																																						
148	H.014267	SAVANNE ROAD OVER HANSON CANAL	6/14/2023	DELATTE, BRIAN	OSTUNO, BARBARA	Terrebonne		OFF																																						
149	H.014270	LEFORT BYPASS ROAD OVER CUT OFF BAYOU	6/14/2023	DELATTE, BRIAN	OSTUNO, BARBARA	Lafourche		OFF																																						
150	H.014273	MONROE FABRE OVER BAYOU DES GLAISES	6/14/2023	DELATTE, BRIAN	OSTUNO, BARBARA	Avoyelles		OFF																																						
151	H.000425	LA 12 SABINE RIVER BRIDGE	7/12/2023	WINDMANN, ANDREW	MASTIN, CATHERINE	Calcasieu	LA 12	ON																																					Project scope not yet determined.	
152	H.001271	CANE RIVER BRIDGE AT CHURCH STREET	7/12/2023	CHEN, YANLIN	MORVANT, RYAN	Natchitoches	LA 1-X	ON	REPLACE	1	59'-11"X430'	86'			298642								3870															1920									
153	H.011992	LA 343: BAYOU QUEUE DE TORTUE BRIDGE	7/12/2023	KREBS, JOHN	RANCK, AMANDA	Lafayette	LA 343	ON		1	160' x 34.5'	40'		1000	56105	8/17/1902																		1800													
154	H.011993	LA 10: BAYOU CARRON BRIDGE	7/12/2023	LANDRY, LAUDUN	TOURRES, VALERIE	St. Landry	LA 10	ON	Replace	1	42.5' x 240'	80'			65000								1200												2000													
155	H.012001	LA 339: CANAL & CREEK BRIDGES	7/12/2023	BOURGEOIS, COREY	LEBAS, MELISSA	Vermilion	LA 339	ON	Replace	3																				150																	
156	H.012005	US80: KCS RR OVERPASS (HBI)	7/12/2023	WANG, XUYONG	RANCK, AMANDA	Caddo	US 80	ON	REPLACE	1	40x150	150	Steel plate girders & rolled shapes	TBD	TBD																			TBD								TBD		TBD			
157	H.012006	LA 1: PRAIRIE RIVER BRIDGE	7/12/2023	GAUDRY, CARL	RANCK, AMANDA	Caddo	LA 1	ON	Replace	1	40x160	20			91164																			3600													
158	H.012009	US 71: MARKET ST BRIDGE OVER ICG RR(HBI)	7/12/2023	GAUDRY, CARL	TOURRES, VALERIE	Caddo	US 71	ON	Replace	1	53'x575'	85		TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	
159	H.012011	LA525, LA173: BOGGY BAYOU AND CR BRIDGES	7/12/2023	DELATTE, BRIAN	BABAIZADEH, HAMED	Caddo	LA 525, LA 173	ON	Replace	2	80x80; 44x220	20			100000																			3500													
160	H.012029	US 80: COOLEY, CROWS, AND CREEK BRS	7/12/2023	DELATTE, BRIAN	BABAIZADEH, HAMED	Bienville, Webster	US 80	ON	Replace	3	40x220; 44x140; 44x120	20			200000																			6000													
161	H.012030	US371: KCS RR OVERPASSES HBI	7/12/2023	GUIDRY, CHRIS	VU, HAI	Webster	LA 159, US 371	ON	REPLACE	3	130X44; 130X48, 130X48	130		600	500000									2470														1680									
162	H.012031	LA 585: DRAINAGE CANAL BRIDGE	7/12/2023	LANDRY, LAUDUN	BAMUGO, ANTHONY	East Carroll	LA 585	ON	Replace	1	32.5' x 80'	20'			30000																			2000													
163	H.012032	LA 2: BRIDGES NEAR MER ROUGE	7/12/2023	HERATH, ANANDA	BAMUGO, ANTHONY	Morehouse, West Carroll	LA 2	ON			42.5x520	20																																		
164	H.012033	LA 143, LA594:CROSS BAYOU & CANEY CR BRS	7/12/2023	GRASSO, PHILLIP	BABAIZADEH, HAMED	Ouachita	LA 143, LA 594	ON	REPLACE	2	32 x 180 & 30 x 80	20			228000																			1200	1950												
165	H.012036	US 80: BOEUF RIVER BRIDGE	7/12/2023	DELATTE, BRIAN	BABAIZADEH, HAMED	Richland	US 80	ON	Replace	1	40x400	80			180000								2000								160			1400		1600											
166	H.012037	US 167,LA2:MIDDLE SLOUGH & CREEK BRIDGES	7/12/2023	DELATTE, BRIAN	BABAIZADEH, HAMED	Union	US 63, LA 2	ON	Replace	2	80x180; 30x40	20			90000																			3000													
167	H.012039	LA 372: CREEK BRIDGE	7/12/2023	BABAIZADEH, HAMED	ALLEN, BRIAN	Allen	LA 372	ON	Replace	1	4'-8' x r r x 48' (Box Culvert)	8		TBD	TBD															48																	
168	H.012040	LA 394 & LA 110: CREEK BRIDGES	7/12/2023	EL KASSOUF, MARK	DELATTE, BRIAN	Beauregard	LA 394, LA 110	ON																																						
169	H.012041	LA 109: GULLY BRIDGE	7/12/2023	WINDMANN, ANDREW	BABAIZADEH, HAMED	Calcasieu	LA 109	ON																						7x6 - 256ft.																	
170	H.012046	CHATLIN LAKE & HORSESHOE CANAL BRIDGES	7/12/2023	GUIDRY, CHRIS	DELATTE, BRIAN	Rapides	LA 1208-1, LA 3170	ON																																					No Info	
171	H.012047	US167: BIG CREEK BRIDGE	7/12/2023	TOURRES, VALERIE	ALLEN, BRIAN	Winn	US 167	ON	replace	1																																			No Information	
172	H.012048	US 84: CASTOR CREEK AND RELIEF BRIDGES	7/12/2023	BUCCI, MARK	DELATTE, BRIAN	LaSalle, Winn	US 84	ON	Replace	2	40'x820', 40'x500'	140'		1,900	475,000									2,880	2,160		1,680												2,900								Est. quantities based on similar projects.
173	H.012057	LA 431:VILLAR CANAL AND DRAINAGE BRIDGES	7/12/2023	EL KASSOUF, MARK	TOURRES, VALERIE	Ascension	LA 431	ON	replace	2	80'x30', 80'x30'	20'			TBD																				TBD												
174	H.012058	LA 8: FORKER CREEK BRIDGE	7/12/2023	GRASSO, PHILLIP	BABAIZADEH, HAMED	Vernon	LA 8	ON			40 x 225	25			210000																			2800													
175	H.012059	LA 19: BRIDGES NEAR ZACHARY	7/12/2023	EL KASSOUF, MARK	BABAIZADEH, HAMED	East Baton Rouge	LA 19	ON	Replace	3	30'x260', 30x120, 30'x100	20																																		
176	H.012061	LA 1: BYU MOREAU AND LATERAL W15#7A BRS	7/12/2023	BRAUNER, KURT	RANCK, AMANDA	Pointe Coupee	LA 1	ON							58800																	1080														
177	H.012072	LA 60: DRAIN BRIDGE	7/12/2023	MUSTAQUE, AHMED	BABAIZADEH, HAMED	Washington	LA 60	ON	Replace	1	TBD																																			
178	H.012537	LA 154: RED CHUTE BAYOU BRIDGE	7/12/2023	CHEN, YANLIN	BABAIZADEH, HAMED	Bossier	LA 154	ON	REPLACE	1	32'X270'	45'			106658							1068												2800													
179	H.012740	I-20: REPLACE FIVE OVERPASSES (LINCOLN)	7/12/2023	GUIDRY, CHRIS	DELATTE, BRIAN	Lincoln	I-20	ON																																					No Info	
180	H.012892	DIST03:ABC BR REPLACE AC,LAF,ST MAR PARS	7/12/2023	BRAUNER, KURT	TULLIER, DANNY	Acadia, Lafayette, St. Martin	LA 1123, LA 321, LA 3116, LA 723	ON																																						
181	H.012893	DIST 04:ABC BR REPLACE BIENVILLE PARISH	7/12/2023	BAMUGO, ANTHONY	TULLIER, DANNY	Bienville	LA 154, LA 501, LA 4, LA 517, LA 518	ON	REPLACE	0																																				
182	H.012894	DIST04:ABC BR REP CLA, WEB PARISHES	7/12/2023	BAMUGO, ANTHONY	TULLIER, DANNY	Claiborne, Webster	LA 3046, LA 146, LA 808, LA 913, LA 524, LA 520, LA 518	ON	REPLACE	0																																				
183	H.012895	DIST05:ABC BR REP E CAR,W CAR,MOR PARISH	7/12/2023	BAMUGO, ANTHONY	TULLIER, DANNY	East Carroll, Morehouse, West Carroll	LA 554, LA 582, LA 580, LA 877, LA 585	ON	REPLACE	0																																				
184	H.012896	DIST04:ABC BR REP BOSS,CADD,RED RIV PARS	7/12/2023	BAMUGO, ANTHONY	TULLIER, DANNY	Bossier, Caddo, Red River	LA 157, LA 155, LA 537, LA 2, LA 169, LA 160, LA 789, LA 783	ON	REPLACE	0																																				
185	H.012897	DIST05:ABC BR REP JACK,LIN,UNION PARISH	7/12/2023	BAMUGO, ANTHONY	TULLIER, DANNY	Jackson, Lincoln, Union	LA 148, LA 144, LA 550, LA 542, LA 507, LA 3061, LA 810, LA 556	ON	REPLACE	0																																				
186	H.012898	DIST05:ABC BR REP OUACHITA, RICH PARS	7/12/2023	BAMUGO, ANTHONY	TULLIER, DANNY	Ouachita, Richland	LA 134, LA 132, LA 576, LA 3048, LA 151, LA 135, LA 838	ON	REPLACE	0																																				

NO.	PROJECT NO.	PROJECT NAME	LETTING DATE	BRIDGE TASK MANAGER	PROJECT MANAGER	PARISH	ROUTE	ON OR OFF SYSTEM	WORK TYPE (NEW/REPLACE, REHA/REPAIR, OTHER)	NO. OF BRIDGES	BRIDGE WIDTH x LENGTH (LIST ALL BRIDGES)	MAX. SPAN LENGTH	STEEL GIRDER TYPE	STRUCTURAL METALWORK IN POUNDS	REINFORCING STEEL IN POUNDS	QUAD BEAM (FT)	TYPE II (FT)	TYPE III (FT)	TYPE IV (FT)	TYPE BT72 (FT)	TYPE BT78 (FT)	LG-25 (FT)	LG-36 (FT)	LG-45 (FT)	LG-54 (FT)	LG-63 (FT)	LG-72 (FT)	LG-78 (FT)	U BEAM (FT)	Culvert/Box (FT)	PILES 12" (FT)	PILES 14" (FT)	PILES 16" (FT)	PILES 18" (FT)	PILES 24" (FT)	PILES 30" (FT)	PILES 36" (FT)	PILES 54" (FT)	DRILLED SHAFT (FT)	STEEL PILES (FT)	STEEL SHEET PILING (SQFT)	NO. OF DISC BEARINGS	OTHER (MSE Wall) (SQFT)	Column1	OTHER (SPECIFY)
187	H.012899	DIST07:ABC BR REP ALLEN, BEA, J DAV PARS	7/12/2023	BRAUNER, KURT	TULLIER, DANNY	Allen, Beauregard	LA 10; LA 27, LA 1147, LA 389	ON																																					
188	H.012900	DIST07:ABC BR REP CALCASIEU, CAMERON PAR	7/12/2023	BRAUNER, KURT	TULLIER, DANNY	Calcasieu, Cameron	LA 3063, LA 384, LA 3256, LA 717	ON																																					
189	H.012909	DIST08:ABC BR REP AVOYELLE, RAPIDES PARS	7/12/2023	GAUDRY, CARL	TULLIER, DANNY	Avoyelles, Rapides	LA 1243, LA 1206, LA 1203, LA 1200, LA 1199, LA 107	ON	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	
190	H.012910	DIST08:ABC BR REP GRAN, NATCH, WINN PARS	7/12/2023	GAUDRY, CARL	TULLIER, DANNY	Grant, Natchitoches, Winn	LA 1226, LA 119, US 167, LA 505, LA 499, LA 472, LA 126, LA 124, LA 1234, LA 1229	ON	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	
191	H.013005	DIST08:ABC BR REP SABINE, VERNON PARS	7/12/2023	GAUDRY, CARL	TULLIER, DANNY	Sabine, Vernon	LA 1215, LA 117, LA 463, LA 399	ON	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	
192	H.013006	DIST58:ABC BR REPL CA,CO,FR,TN,LA PARISH	7/12/2023	GAUDRY, CARL	TULLIER, DANNY	Catahoula, Concordia, Franklin, LaSalle, Tensas	LA 126, LA 124, LA 778, LA 772, LA 605, LA 577, LA 569, LA 568, LA 135, LA 127	ON	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	
193	H.013007	DIST62:ABC BR REPLACE TANGIPAHOA PARISH	7/12/2023	BOURGEOIS, COREY	TULLIER, DANNY	Tangipahoa	LA 442, LA 40, LA 38, LA 1062, LA 1061, LA 1054	ON	Replace																																				
194	H.013008	DIST62:ABC BR REPLACE ST TAM,WASH PARS	7/12/2023	BOURGEOIS, COREY	TULLIER, DANNY	St. Tammany, Washington	LA 1129, LA 1072, LA 59, LA 450, LA 438, LA 436, LA 434, LA 36, LA 16	ON	Replace																																				
195	H.013009	DIST03:ABC BR REP EV,ST LA,IB,VER PARS	7/12/2023	BRAUNER, KURT	TULLIER, DANNY	Evangeline, Iberia, St. Landry, Vermilion	LA 104, LA 85; LA 2925, LA 752; LA 700, LA 682, LA 358, LA 3187, LA 3149	ON																																					
196	H.013010	DIST62:ABC BR REPL LIVING, ST HELENA PAR	7/12/2023	BOURGEOIS, COREY	TULLIER, DANNY	Livingston, St. Helena	LA 63, LA 449, LA 38, LA 37, LA 1047, LA 1042, LA 1032, LA 1027	ON	Replace																																				
197	H.013011	DIST58: ABC BR REPLACE CALDWELL PARISH	7/12/2023	GAUDRY, CARL	TULLIER, DANNY	Caldwell	LA 850, LA 506, LA 4, LA 127, LA 126	ON	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	TBD	
198	H.013012	DIST61:ABC BR RP AC,AS,E FL,P CO,WBR PAR	7/12/2023	BRAUNER, KURT	TULLIER, DANNY	Ascension, Assumption, East Feliciana, Pointe Coupee, West Baton Rouge	LA 308, LA 81; LA 621, LA 986, LA 970, LA 963, LA 943, LA 935, LA 934	ON																																							
199	H.014258	LA 1:PORT ALLEN CANAL BR REPL (PH2)(HBI)	7/12/2023	ALLEN, BRIAN	DELATTE, BRIAN	West Baton Rouge	LA 1	ON	Replace	1	72.5 x 2700	350	Steel plate girders	6734516	3158771												9902	5985				173		33750	17480	1344	903					28	6295		
200	H.014259	LA 37: SANDY BYU AND HUBS CREEK BRIDGES	7/12/2023	KREBS, JOHN	RANCK, AMANDA	East Baton Rouge	LA 37	ON		2	280' x 42.5'; 100' x 42.5'	70'		1000	160500								1400																						198.2 CY (Slab Span Concrete)
201	H.013034	US 80: I-20 INTERCHANGE (GREENWOOD)	10/11/2023	BOOTHE, JOHN	MORVANT, RYAN	Caddo	US 80	ON	Replace	1	40'x355'	100'		600	150,000								960	1,200											1520				1,120							Est. quantities based on similar projects.
202	H.008230	LA 838: STEEP BAYOU BRIDGE REPLACEMENT	11/8/2023	GUIDRY, CHRIS	BABAZADEH, HAMED	Ouachita	LA 838	ON	REPLACE	1	100X34.5	20		100	39197																				1060										
203	H.016885	LA 91: BAYOU PLAQUEMINE BRULE BR REPLACE	11/8/2023	BRAUNER, KURT	MOSS, SARAH	Acadia	LA 91	ON						2000	100000								1600												2160										
204	H.014059	US 80: BRIDGES NEAR MINDEN	12/13/2023	DELATTE, BRIAN	ISEMANN, ROBERT	Bossier, Webster	US 80	ON	Replace	8	42.5x120; 42.5x100; 42.5x100; 42.5x300; 42.5x340; 42.5x260; 46.5x90	40			714400							395												33750											
205	H.000986	SABINE RIVER BR (BURR FERRY)	12/19/2023	WINDMANN, ANDREW	MORVANT, RYAN	Vernon	LA 8	ON																																					Project scope not yet determined.