

# TABLE OF CONTENTS

---

<b>TOPIC</b>	<b>PAGE</b>
<b>Quality Assurance</b> .....	1
Field Curve .....	2
Contractor's Responsibilities - Quality Control (QC) .....	2
Personnel .....	3
Dimensional Control .....	4
Material Quality .....	4
Sampling and Testing .....	4
Construction Layout .....	5
Traffic Control .....	6
Responsibilities of the Project Engineer .....	6
Monitoring of Quality Control (QC) .....	6
Inspection .....	7
Personnel .....	7
Construction Layout .....	7
Equipment .....	7
Acceptance .....	8
Visual Inspection .....	8
Sampling and Testing .....	8
Traffic Control .....	9
Responsibilities of the District Laboratory .....	9
Responsibilities of the Materials and Testing Section .....	10
Dedicated Stockpiles .....	10
Nondedicated Stockpiles .....	11
Environmental Protection .....	11
Erosion Control .....	11
<b>Certification</b> .....	15
Personnel .....	15
General Certification Requirements .....	15
Department Personnel .....	15
Nondepartment Personnel .....	15
Equipment .....	16
Central Mix Plant .....	16
Revocation of Plant Certification .....	17
Scale and Meter Calibration .....	17
Feed Bin Calibration Curves .....	18
Construction Equipment .....	18

# TABLE OF CONTENTS

---

<b>TOPIC</b>	<b>PAGE</b>
<b>Clearing and Grubbing - Section 201</b> .....	19
Equipment.....	19
Construction Practices .....	19
Vegetation on Private Property .....	20
Disposal of Excess Material.....	20
Inspections for Hazardous Substances, and Archaeological or Paleontological Remains .....	21
Hazardous Materials .....	21
Archaeological or Paleontological Inspections.....	21
Burning Vegetation .....	22
Selective Clearing.....	23
Quality Assurance Documentation.....	23
Quality Control .....	23
Inspection and Acceptance .....	24
<b>Removing or Relocating Structures and Obstructions - Section 202</b> .....	25
Quality Assurance Documentation.....	26
<b>Excavation and Embankment - Section 203</b> .....	27
Excavation .....	27
Excavation Outside the Right-of-Way.....	27
Disposal of Excess or Unusable Materials.....	27
Equipment.....	28
General Excavation .....	28
Undercutting .....	28
Drainage Excavation.....	28
Muck Excavation.....	28
Embankment.....	29
Embankment Constructed with Usable or Lime Modified Soils .....	29
Soil Usage Table.....	29
Soil Boring Information.....	30
Soil Quality Inspection .....	30
Soils With Swell Potential .....	30
Borrow.....	30
Embankment Constructed With Aggregates – Non Plastic Embankment .....	31
Plastic Soil Blanket .....	32
Stabilization With Geotextile Fabric .....	33
Equipment.....	33
Quality Assurance (QA) .....	34
Existing Surface Preparation for Embankments, Bases and Subbases - Chart.....	35
Transitions from Cut to Fill .....	36
Quality Control (QC) .....	36
Inspection and Acceptance.....	37

# TABLE OF CONTENTS

---

<b>TOPIC</b>	<b>PAGE</b>
<b>Excavation and Embankment, Section 203, Continued</b>	
Visual Inspection.....	38
Quality Assurance Documentation.....	39
Density & Moisture Content Worksheet.....	39
<b>Temporary Erosion Control - Section 204</b> .....	41
Equipment.....	41
Temporary Seeding .....	41
Temporary Mulching .....	42
Sandbagging.....	42
Baled Straw or Hay .....	42
Slope Drains .....	42
Sediment Basins.....	43
Sediment Check Dams .....	43
Silt Fencing .....	43
Berms.....	43
Temporary Construction Entrance .....	44
Quality Assurance Requirements .....	44
<b>Class I Base Course - Section 301</b> .....	45
Materials .....	45
Asphaltic Concrete and Portland Cement Concrete .....	45
Treated Layer Under Asphaltic Concrete.....	45
Aggregates to be Used Without Stabilization.....	46
Materials to be Used With Stabilization .....	46
Materials Specification Requirements for Soil Cement - Chart.....	46
Design.....	47
Storage and Handling of Materials.....	48
Stockpiles .....	48
Cement .....	48
Water .....	49
Equipment.....	49
Asphaltic Concrete and Portland Cement Concrete .....	49
Production Equipment.....	49
Transport Equipment .....	49
Raw Base Course .....	49
Stabilized Base Course .....	49
Placement and Spreading Equipment .....	50
Compaction Equipment .....	50
Raw Base Course.....	50
Stabilized Base Course .....	50
Finishing Equipment .....	51
Water Trucks .....	51
Asphalt Distributor .....	51

# TABLE OF CONTENTS

---

TOPIC	PAGE
<b>Class I Base Course - Section 301, Continued</b>	
Construction Details.....	51
Plant Operations.....	51
Weather Limitations.....	52
Stockpiles.....	52
Feeder System.....	53
Mixing System.....	54
Calibration and Feed Tolerances - Chart.....	54
Transport.....	55
Plant Lot.....	55
Quality Assurance Requirements.....	55
Quality Control (QC).....	55
Raw Base Course.....	55
Treated Layer Under Asphaltic Concrete.....	55
Cement Stabilized Base Courses.....	55
Inspection and Acceptance.....	57
Roadway Operations.....	58
Placement and Spreading.....	58
Joint Construction.....	58
Compaction.....	58
Cement Stabilized Base.....	58
Treated Layer Under Asphaltic Concrete.....	59
Raw Aggregate Base.....	59
Finishing.....	59
Cement Stabilized Base.....	59
Raw Aggregate Base.....	60
Treated Layer Under Asphaltic Concrete.....	60
Quality Assurance.....	60
Quality Control (QC).....	60
Stabilized and Raw Base Course.....	60
Treated Layer Under Asphaltic Concrete.....	61
Inspection and Acceptance.....	61
Stabilized and Raw Base Course.....	61
Visual Inspection.....	62
Treated Layer Under Asphaltic Concrete.....	62
Protection and Curing.....	62
Soil Cement, Cement Stabilized Sand Clay Gravel, Cement Stabilized Sand-Shell, or Treated Layer Under Asphaltic Concrete.....	62
Stone, Crushed Slag, or Recycled PCC.....	63
Maintenance of the Base Course.....	63
Quality Assurance Documentation.....	63
Central Mix Plant Certification Report.....	63
Soils/Soil-Aggregate Form and Aggregate Test Report.....	64

# TABLE OF CONTENTS

---

<b>TOPIC</b>	<b>PAGE</b>
<b>Class I Base Course - Section 301, Continued</b>	
Base Course Design for Class One Base Course .....	64
Contractor's Proposal .....	64
Department Approval .....	64
Daily Central Mix Plant Report.....	65
Gradation and Soil Properties.....	65
Proportioning of Components .....	65
Additive Content .....	65
Moisture Content .....	66
Acceptance Tests .....	66
Certificate of Material Components (Haul Ticket).....	66
Central Mix Plant .....	66
Density & Moisture Content Worksheet.....	67
Payment.....	67
Acceptance Without Payment Adjustment.....	67
Acceptance With Payment Adjustment.....	67
Example of Cumulative Payment Adjustment - Per Section .....	67
Example of Cumulative Payment Adjustment Partial Section Affected by Cement .....	68
Removal and Replacement of Stabilized Base.....	68
<b>Class II Base Course - Section 302 .....</b>	<b>69</b>
Materials .....	69
Storage and Handling of Materials.....	69
Stockpiles .....	69
Cement .....	69
Design .....	70
Traffic Control.....	70
Equipment.....	71
Cement Spread Rate .....	71
Quality Assurance.....	72
Quality Control (QC) .....	72
Asphaltic Concrete and Portland Cement Concrete .....	72
Subgrade Layer .....	72
Raw Base Course.....	72
Stabilized or Treated Base Course.....	72
Placement of Base Material.....	73
Density Before Mixing With Cement.....	73
Pulverization .....	73
Weather Limitations.....	73
Moisture Content After Initial Compaction and Prior to Spreading Cement .....	74
Spreading Cement.....	74

# TABLE OF CONTENTS

---

<b>TOPIC</b>	<b>PAGE</b>
<b>Class II Base Course - Section 302, Continued</b>	
Cement Spread Rate and Length .....	75
In-Place Mixing .....	75
Moisture Content After Mixing With Cement.....	75
Protection and Curing .....	76
Maintenance of the Base Course .....	76
Inspection and Acceptance.....	76
Visual Inspection.....	76
Density Before Mixing With Cement .....	77
Cement Spread Rate and Length .....	77
Pulverization .....	77
Moisture Content .....	77
Raw Bases.....	77
Prior to Spreading Cement .....	77
After Spreading Cement .....	78
Density.....	78
Grade, Cross Slope, Thickness and Width .....	78
Quality Assurance Documentation.....	78
General .....	78
Quality Control .....	79
Contractor Documentation.....	79
Inspection and Acceptance.....	80
Density & Moisture Content Worksheet .....	80
Fieldbook .....	80
<b>In-Place Stabilized Base Course - Section 303 .....</b>	<b>81</b>
Materials .....	81
Asphaltic Concrete and Portland Cement Concrete .....	82
Cement.....	82
Design.....	82
Traffic Control .....	83
Equipment.....	84
Cement Spreader .....	84
In-Place Mixer .....	84
Compaction Equipment.....	85
Water Trucks .....	85
Finishing Equipment .....	85
Asphalt Distributor .....	85
Preparation of Roadbed.....	86
Surface Removal .....	86
Scarification, Blending and Pulverization.....	86
Shaping and Initial Compaction .....	87
Moisture Content After Initial Compaction and Prior to Spreading Cement .....	87

# TABLE OF CONTENTS

---

<b>TOPIC</b>	<b>PAGE</b>
<b>In-Place Stabilization- Section 303, Continued</b>	
Quality Control .....	87
Stabilization.....	87
Weather Limitations .....	87
Spreading Cement.....	88
Cement Spread Rate and Length .....	88
Quality Control .....	88
Inspection and Acceptance.....	89
In-Place Mixing.....	89
Moisture Content After Mixing With Cement.....	89
Quality Control .....	89
Thickness and Width.....	90
Quality Control .....	90
Inspection and Acceptance .....	90
Compacting and Finishing .....	90
Quality Control .....	90
Protection and Curing .....	91
Maintenance of the Base Course.....	91
Inspection and Acceptance.....	92
DOTD TR 602 Measurements .....	93
Visual Inspection.....	93
Quality Assurance Documentation.....	93
<b>Lime Treatment - Section 304 .....</b>	<b>95</b>
Types and Uses of Lime Treatment - Chart.....	95
Materials .....	95
Equipment.....	96
Spreading Equipment .....	96
Mixing Equipment .....	96
Water Trucks .....	96
Compaction Equipment.....	96
Special Traffic Considerations .....	97
Type B Treatment .....	97
Mixing Equipment (Type B).....	97
Construction Details (Type B).....	97
Protection and Curing (Type B) .....	98
Quality Assurance.....	98
Quality Control (QC) (Type B) .....	98
Inspection and Acceptance (Type B).....	99
DOTD TR 602 Measurements (Type B) .....	100
Visual Inspection (Type B).....	100

# TABLE OF CONTENTS

---

<b>TOPIC</b>	<b>PAGE</b>
<b>Lime Treatment - Section 304, continued</b>	
Type C Treatment.....	101
Mixing Equipment (Type C) .....	101
Construction Details (Type C).....	101
Quality Assurance (Type C).....	101
Quality Control (QC) (Type C) .....	101
Inspection and Acceptance (Type C).....	101
Type D Treatment.....	102
Mixing Equipment (Type D) .....	102
Construction Details (Type D).....	102
Protection and Curing (Type D) .....	102
Quality Assurance.....	103
Quality Control (QC) (Type D) .....	103
Inspection and Acceptance (Type D).....	103
Type E Treatment .....	103
Mixing Equipment (Type E).....	103
Construction Details (Type E).....	103
Protection and Curing (Type E) .....	103
Quality Assurance.....	104
Quality Control (QC) (Type E) .....	104
Inspection and Acceptance (Type E).....	104
Quality Assurance Documentation .....	104
Quality Control.....	104
Inspection and Acceptance.....	104
Density & Moisture Content Worksheet.....	104
<b>Subgrade Layer - Section 305</b> .....	105
<b>Materials</b> .....	105
Asphaltic Concrete.....	105
Portland Cement Concrete .....	105
Aggregates for Aggregate Subgrade Layer .....	105
Blended Calcium Sulfate .....	105
Soils for Treated Subgrade Layer .....	106
Cement .....	106
Water .....	106
<b>Equipment</b> .....	106
<b>Construction Details</b> .....	106
Subgrade Layer Constructed With Asphaltic Concrete.....	106
Subgrade Layer Constructed With Aggregate .....	107
Subgrade Layer Constructed With Treated Soils.....	107
Subgrade Layer Constructed With Blended Calcium Sulfate .....	107



# TABLE OF CONTENTS

---

<b>TOPIC</b>	<b>PAGE</b>
<b>Subgrade Layer– Section 305, continued</b>	
Quality Assurance.....	107
Quality Control (QC) .....	107
Inspection and Acceptance.....	107
Quality Assurance Documentation.....	107
<b>Scarifying and Compacting Roadbed - Section 306</b> .....	109
Materials .....	109
Equipment.....	109
Construction Details.....	109
Quality Assurance.....	110
Quality Control (QC).....	110
Inspection and Acceptance .....	110
Specification Density Requirements for Base and Subbase - Chart.....	110
Visual Inspection .....	110
Quality Assurance Documentation .....	111
Quality Control .....	111
Inspection and Acceptance.....	111
Density & Moisture Content Worksheet.....	111
Maintenance .....	111
<b>Culverts and Storm Drains - Section 701</b> .....	113
Trench Excavation and Bedding .....	113
Shoring .....	114
Backfill Materials.....	114
Sidedrains - Nonpaved Areas .....	114
Plastic Pipe .....	114
Pipe Other Than Plastic Pipe.....	115
Sidedrains - Paved Areas .....	115
Pipes Other Than Sidedrains.....	115
Plastic Pipe .....	115
Corrugated Metal Pipe .....	115
Pipe Other than Plastic or Corrugated Metal .....	115
Construction Details.....	115
Side Drains Under Unpaved Areas.....	116
Pipes Other Than Side Drains and	
Side Drains Under Paved Areas .....	116
Top of Pipe Even With or Below Top of Trench .....	116
Top of Pipe Above Top of Trench .....	116
Compaction.....	116
Selected Soils .....	117
Granular Material .....	117

# TABLE OF CONTENTS

---

<b>TOPIC</b>	<b>PAGE</b>
<b>Culverts and Storm Drains - Section 701, continued</b>	
Quality Assurance.....	117
Quality Control.....	117
Inspection and Acceptance.....	117
<b>Manholes, Junction Boxes and Catch Basins - Section 702</b> .....	119
Quality Assurance.....	119
<b>Structural Excavation and Backfill - Section 802</b> .....	121
Shoring.....	121
Box Culverts.....	121
Backfilling.....	122
Selected Soils .....	122
Granular Material .....	123
Cofferdams and Cribs .....	123
Footings .....	123
Other Structures.....	123
Quality Assurance.....	123

# TABLE OF CONTENTS

---

<b>TOPIC</b>	<b>PAGE</b>
Borrow Pit Sketch - Example .....	A - 1
Plant Certification Sticker .....	A - 3
Base Course Central Mix Plant Certification Report (03-22-0753) .....	A - 5
Certification Report for Scales and Meters (03-22-3065).....	A - 11
Transition from Cut to Fill - Example Sketch.....	A - 13
Base Course Design for Central Plant Materials Mixtures (03-22-0752) .....	A - 15
Feed Bin Calibration Curves - Example .....	A - 17
Daily Central Mix Plant Report (03-22-0754) .....	A - 19
Certificate of Material Proportions for Base Course (03-22-0751) .....	A - 21
Density & Moisture Content Worksheet (03-22-0750) .....	A - 23
Right of Entry .....	A - 25
Certificate of Release.....	A - 27
Pollution Prevention Certification Statement.....	A - 29
Notice of Intent.....	A - 31
Notice of Termination.....	A - 33
J-Stitch Sketch for Geotextile Fabric.....	A - 35
Inspection Report - Archaeological or Hazardous Materials (excerpt EDSM III.1.1.22).....	A - 37