

SECTION 713 TEMPORARY SIGNS, BARRICADES & PAVEMENT MARKINGS

MATERIAL		REFERENCE	PURP.	SAMPLED BY	MIN. FREQ.	MIN. QUANT.	CERT.	SMALL QUANTITY	TYPICAL HANDLING TIME	REMARKS
		TESTED BY		METHOD		CONTAINER	DISTR.			
ADVANCE WARNING ARROW PANEL		713.04(b) Proj. Engr.	Accept.	-----	-----	-----	-----	-----	-----	Visual inspection by Proj. Engr.
BARRICADE WARNING LIGHTS		713.02 1018.12 Mat. Lab	Accept.	Proj. Engr. S 601	1/type*	1 unit	CC** 1	----	-----	(QPL 16) *Visual inspection by Proj. Engr. Sample only if questionable. **See Specification Subsection 1018.12(c) for certification requirements.
DRUMS		Std. Pl. HS-01 Proj. Engr.	Accept.	-----	-----	-----	CC 1	-----	-----	(QPL 38 for plastic drums) Visual inspection by Proj. Engr. Sample only if questionable.
	Sheeting	713.02 1015.05(e) Proj. Engr.	Accept.	Proj. Engr. S 601	-----	-----	CC 1	-----	-----	(QPL 13) Visual inspection by Proj. Engr. Sample only if questionable.
GLASS BEADS FOR THERMOPLASTIC PAVEMENT MARKINGS AND TRAFFIC PAINT	Drop-on Application	713.05 1015.05(e) Mat. Lab	Prelim. Source Approval	Dist. Lab or other state agencies	1/lot	1-50 lb bag	-----	-----	10 days	-----
		713.05 1015.13 Mat. Lab	Accept.	-----	-----	-----	CD* 1 & 7	-----	10 days	*CD issued when presampled by Dist. Lab.
PORTABLE FLASHER SUPPORTS		Std. Pl. HS-01 Proj. Engr.	Accept.	-----	-----	-----	-----	-----	-----	Visual inspection by Proj. Engr.
RAISED PAVEMENT MARKERS & ADHESIVES		713.02 1015.09 Mat. Lab	Accept.	SEE SECTION 731 OF THIS MANUAL.						
TEMPORARY PAVEMENT MARKING TAPE	Temporary Striping Tape (Type I & II)	1015.08 Mat. Lab	Accept.	Proj. Engr. S 601	1/shipment*	6 ft length	CC 1	-----	10 days	(QPL 60) *Visual inspection by Proj. Engr. Sample only if questionable.

I-82 5/99

SECTION 713 TEMPORARY SIGNS, BARRICADES & PAVEMENT MARKINGS (Cont'd)

MATERIAL		REFERENCE	PURP.	SAMPLED BY	MIN. FREQ.	MIN. QUANT.	CERT.	SMALL QUANTITY	TYPICAL HANDLING TIME	REMARKS
		TESTED BY		METHOD		CONTAINER	DISTR.			
TEMPORARY SIGNS & BARRICADES	Backing Materials	713.02 1015.04(b) Const. Fab. Insp.	Accept.	Inspected and approved by Const. Fab. Insp. to indicate approval at time of fabrication only.			CA/CC* 6	-----	-----	Visual inspection by Proj. Engr. for acceptance. *CA for aluminum, CC for wood.
	Barricades, Signs & Vertical Panels	Std. Pl. HS-01 Const. Fab. Insp.	Accept.	Inspected, approved and stamped by Const. Fab. Insp. to indicate approval at time of fabrication only.			-----	-----	-----	Visual inspection by Proj. Engr. for acceptance.
	Sheeting Material	1015.05 1015.06 Std. Pl. HS-01 Mat. Lab	Accept.	Inspected and approved by Const. Fab. Insp. to indicate approval at time of fabrication only. See Section 729 of this manual.			CA 6	-----	-----	(QPL 13) Visual inspection by Proj. Engr. for acceptance.
THERMOPLASTIC PAVEMENT MARKINGS		713.02 Mat. Lab	Accept.	SEE SECTION 732 OF THIS MANUAL.						
TRAFFIC PAINT		713.02 Mat. Lab	Accept.	SEE SECTION 737 OF THIS MANUAL.						