

SUMMARY OF ESTIMATED QUANTITIES

ITEM	DESCRIPTION	UNIT	QUANTITY
736-06-00100	Signal Service	EACH	1
736-06-00200	Signal Service (Pedestal Required)	EACH	1
736-08-00071	Sig Cntrlr (TS-2, Type 2, w/Eth cap)(Type 6E Cabinet) (F&I)	EACH	1
736-09-00100	Loop Detector	LNFT	350
736-10-00200	Underground Junction Box (Type E)	EACH	3
736-10-00300	Underground Junction Box (Type F)	EACH	3
736-10-00400	Underground Junction Box (Type G)	EACH	1
736-11-00100	Conduit (1/2" HDPE, Schedule 80)	LNFT	43
736-11-00300	Conduit (2" HDPE, Schedule 80)	LNFT	985
736-11-00400	Conduit (3" HDPE, Schedule 80)	LNFT	280
736-12-01001	Conductor (2c, Loop Lead in, imsa 50-2, #14 awg, Twisted Pair)	LNFT	1,222
736-12-02000	Conductor (3c, 6 gauge / #6 awg)	LNFT	47
736-12-04000	Conductor (6c, #14 awg)	LNFT	324
736-12-06000	conductor (10c, #14 awg)	LNFT	1,323
739-01-00100	Hydro-Seeding	ACRE	2
740-01-00100	Construction Layout	LUMP	LUMP
NS-200-00020	Cleaning Existing Ditches	LNFT	140
NS-500-00340	Saw Cutting Asphaltic Concrete Pavement	INLF	22,374
NS-600-00220	Saw Cutting Portland Cement Concrete Pavement	INLF	17,089
NS-736-00001	GPS	EACH	1
NS-736-00005	Video Detection Cabinet Components	EACH	1
NS-736-00006	Video Detection Camera	EACH	4
NS-MSC-00120	Drainage Structure [ADJUST/CONVERT EXIST. C.B. TO M.H.]	EACH	10

Figure 8-17b: Summary of Estimated Quantities



SUMMARY OF ESTIMATED QUANTITIES



DATE SHEET: 7/24/15
2 OF 2

PARISH: ASCENSION
CONTROL SECTION: 265-02 & 803-12
STATE PROJECT: H.009033.6

SHEET NUMBER: 3C