## **NOTES**

FOR ADDITIONAL INFORMATION ON GUARD RAIL, SEE STANDARD PLANS FOR HIGHWAY GUARD RAIL

ALL TIMBER SHALL BE TREATED SOUTHERN YELLOW PINE OR DOUGLAS FIR. (CUT TO FIT). ALL HARDWARE & NAILS INVOLVED SHALL BE REPLACED WITH NEW MATERIALS AND SHALL BE GALVANIZED.

POST SPACING VARIES FROM STRUCTURE TO STRUCTURE. ORIGINAL POST SPACING SHALL BE VERIFIED BY THE PROJECT ENGINEER AND NEW POSTS SHALL BE PLACED AT THESE LOCATIONS. ANY POST AT OTHER THAN THE ORIGINAL POST SPACING SHALL BE REMOVED.

GUARD RAIL SPLICES SHALL BE MADE AT POST LOCATIONS ONLY. LAP IN DIRECTION OF TRAFFIC.

\* HOLES IN CONCRETE CURB SHALL BE COUNTER-SUNK SO THE BOLT HEAD WILL NOT PROTRUDE OUTSIDE THE FACE OF CURB. GROUT HOLES WITH APPROPRIATE MATERIAL AFTER BOLT HAS BEEN TIGHTENED.


ALL WORK AND MATERIALS REQ'D. TO COMPLETE GUARD RAIL ON BRIDGE SHALL BE PAID FOR UNDER ITEM 704-01-01020 GUARD RAIL, (SINGLE THRIE BEAM) (6'-3" POST SPA.) PER LIN. FT.

WHEN EXTERIOR STRINGER IS REQ'D. TO BE REPLACED IT SHALL BE DONE AS DIRECTED BY THE PROJECT ENGINEER AND PAID FOR UNDER FORCE ACCOUNT.

□ ALL %"ø BOLTS SHALL BE ASTM A307.

ALL BOLT LENGTHS SHALL BE VERIFIED BY FIELD MEASUREMENTS.

THIS DETAIL WAS DEVELOPED AND APPROVED FOR USE UNDER NCHRP REPORT 350. AS PER LADOTD'S MASH IMPLEMENTATION POLICY, ITS CONTINUED USE IS ALLOWED WHILE A MASH ALTERNATIVE IS DEVELOPED OR EVALUATED.



M.

CONTROL

a. o. ⇒ a. ×

CHECK
CHECK
CHECK
CHECK
REVIEW

KURT M. BRAUNER License No. 30567 PROFESSIONAL ENGINEER

IN IN ENGINEERING

74/22/22

GUARD RAIL REHABILITATION (CONCRETE DECK)

DOTD BRIDGE AND STRUCTURAL DESIGN