

# PILOT FORCE ACCOUNT PROGRAM


Low-Cost Safety Countermeasures for Roadway Departure Crashes



### History

- Request to initiate force account work for safety and pavement preservation in 2010 (LADOTD)
- Pilot considered for safety ONLY as part of the SHSP (FHWA 6/1/10)
- 23 CFR 635.104 and 635.202
  - Identify, locate, describe project(s)
  - Type of safety materials
  - Cost effectiveness
- Tracking mechanism needed

#### SHSP Roadway Departure




#### Identifying Locations

- Systematic approach
- 2-lane rural
- Width > 22'
- 5 crashes/yr/route/Dist
- ≥ 50% RwD crashes
- Prioritized by # of RwD crashes in 3 yrs
- Segmented by tangent/curve

### Eligible Materials


- Paint
- Glass beads
- Retro-reflective sign sheeting
- Sign posts
- Sign stabilizers
- Retro-reflective RPMs in tangents
- Epoxy

### **Tangent Typical**




| Item                                     | Cost per Unit | Quantity | Units       | Total Cost |
|--|---------------|----------|-------------|------------|
| 4" solid white                           | \$201.12      | 2        | mile        | \$402.24   |
| 4" broken yellow                         | \$69.12       | 1        | mile        | \$69.12    |
| Labor and Equipment per Mile of Striping | \$25.12       | 3        | mile        | \$75.36    |
| Glass Beads                              | \$90.00       | 2.25     | mile        | \$202.50   |
| RPM (yellow)                             | \$0.69        | 132      | quantity    | \$91.08    |
| RPM (white/red)                          | \$0.69        | 1056     | quantity    | \$728.64   |
| Ероху                                    | \$0.89        | 297      | pound       | \$264.33   |
| Labor and Equipment per RPM              | \$0.48        | 1188     | quantity    | \$570.24   |
| TOTAL COST PER TANGENT MILE              |               |          | GRAND TOTAL | \$2,403.51 |

### Curve Typical (Signs & Striping)



### Curve Typical (RPM)



#### Latest Research

- Chevrons and curve warning signs
  - CMF = 0.59
- Doubled up
- Increased sign size
- Centerlines and edge lines
- RPM???

#### Case Study – LA 1019

- Before: 12' lanes, no shoulders
- After: Overlay, 12' lanes, 2' shoulders, centerline rumble strips, enhanced signing and striping/RRPMs (doubled-up at 10' spacing)

## Case Study - LA 1019

| Crash Rate            | Before | After |
|-----------------------|--------|-------|
| Total                 | 6.29   | 4.07  |
| ROR                   | 1.87   | 1.07  |
| Wet Weather           | 2.77   | 0.46  |
| Nighttime             | 1.94   | 1.09  |
| Nighttime ROR         | 0.65   | 0.50  |
| Nighttime Wet Weather | 0.92   | 0.14  |

# Case Study – LA 1019

| Condition                | Observed<br>Crashes | Expected<br>Crashes | Expected<br>Crash Rate | CMF? |
|--------------------------|---------------------|---------------------|------------------------|------|
| Before (w/out CL rumble) | 68                  | 67.88               | 5.6                    |      |
| Before (w/ CL rumble)*   | 57                  | 56.3                | 4.64                   | 0.83 |
| After                    | 33                  | 36.52               | 3.01                   | 0.65 |


<sup>\*</sup>Crashes correctable by centerline rumble strips were removed from the data set.

#### Cost Effectiveness

| Item                           | DOTD Cost* | Contractor Cost | Quantity | Total DOTD Cost | Total Contractor<br>Cost |
|--------------------------------|------------|-----------------|----------|-----------------|--------------------------|
| Cost per Mile,<br>Tangent      | \$2,833.92 | \$6,264.62      | 766.4    | \$2,171,916.29  | \$4,801,204.77           |
| Cost per Curve,<br>Sign/Stripe | \$3,255.20 | \$6,664.65      | 1285.0   | \$4,182,925.58  | \$8,564,075.25           |
| Cost per Curve<br>Mile, RPM    | \$4,441.80 | \$3,743.52      | 119.6    | \$531,239.28    | \$447,724.99             |
| GRAND TOTAL                    |            |                 |          | \$6,886,081.14  | \$13,813,005.01          |

<sup>\*</sup>Includes materials, equipment and labor (w/ benefits factor)

### Implementation Process



#### Authorization

- HQ Safety
- District-wide project numbers H.967XXX
- Budget request
- HQ Safety will notify the DTOE
- WHEN?

#### DISTRICT INPUT NEEDED HERE

#### Site Investigation

- Curve speed study form
- Passing zone verification
- Document any exceptions
- Adjustment to quantities
- FHWA MUST APPROVE ALL EXCEPTIONS!

#### Purchase Materials

- Upon approval of any exceptions, if applicable, the DTOE can order the materials through statewide contracts
- OR Section 45 can place the order

DISTRICT INPUT NEEDED HERE

#### Work Request

- Through Agile Assets
- By Route
- Must be associated with H.967XXX
- Notification sent to HQ Safety and FHWA
- MUST BE INSTALLED WITHIN 6 MONTHS!!!

#### Work Orders

- DTOE provides oversight.
- Multiple work orders may be associated with a work request.
- Once all work orders are complete, DTOE will close the work request.
- Notification sent to HQ Safety and FHWA.

### **Quality Assurance**

- Section 45?
- DTOE?

DISTRICT INPUT NEEDED HERE

#### Close Out

- Reimbursement will NOT occur if ALL elements are not completed within 6 months
- Back into District Traffic Budget, not replaced
- Pilot will be evaluated by FHWA before consideration of expansion of force account program

#### Safety Effectiveness Evaluation

- 3 years before and after
- Research project to evaluate RPM effectiveness in Louisiana

### Legal Ruling

 This document has undergone a legal review by the Louisiana Department of Transportation and Development's General Counsel and the proposed activities set forth in this document are deemed allowable under Title 48.

#### Questions/Comments

- A questionnaire will be sent out to the DTOEs
- Please discuss with your DA